



April 12, 2024

(2 pages)

**ADDENDUM NO. 02**

**REFERENCE NO. 2024-18-T  
LEARNING COMMONS RENOVATIONS AT WOODMAN-CAINSVILLE SCHOOL,  
AGNES G. HODGE PUBLIC SCHOOL AND SIMCOE COMPOSITE SCHOOL  
FOR THE GRAND ERIE DISTRICT SCHOOL BOARD**

---

**This Addendum is part of the Bid Document.**

**Clarification:**

1. Correction to answer on question 24 from Addendum 1:
- Q24 Confirm door infill area around new door at Agnes G. Hodge to receive painted brick at vestibule side, & drywall finish at library side.
- A24 ~~This scope is being removed as part of this addendum.~~

**Correct answer: Confirmed.**

**QUESTIONS AND ANSWERS**

- Q1 Structural lintel rework may be required to widen existing Woodman door from 36" to 38". Are we to include for this & are existing structural drawings available? Also, is cutting & finishing existing masonry acceptable?
- A1 Yes, include for this & there are no drawings available. Yes, cutting and finishing is acceptable.**
- Q2 Agnes G Hodge drawing indicates new W2 walls in same location of existing ... is the intent to replace existing walls?
- A2 W2 - 1/2" Type-x Gypsum Board, Tape and Seal all Joints laminated onto existing block walls with Lepage PL Premium Max Construction Adhesive**

Woodman- Cainsville School

- Q3 How many existing emergency lights would need to be changed?
- A3 Replace existing.**

Q4 Are we installing new receptacles or replacing existing receptacles with new ones?

**A4 Allow for the installation of fifteen (15) new duplex receptacles utilizing existing room circuits. As per specifications. Include one (1) dedicated circuit for tablet charging cart.**

Agnes G. Hodge Public School Scope of Work

Q5 Do we have a count on how many existing emergency lights would need to be changed?

**A5 Replace existing.**

Q6 Are we installing new receptacles or replacing existing receptacles with new ones?

**A6 Allow for the installation of sixteen (16) new duplex receptacles utilizing existing room circuits. As per specifications. Include one (1) dedicated circuit for tablet/laptop charging cart.**

Simcoe Composite School

Q7 Are we installing new receptacles or replacing existing receptacles with new ones?

**A7 Allow for the installation of fifty (50) new duplex receptacles utilizing existing room circuits. As per specifications. GEDSB to approve receptacle locations."**

Q8 How many ceiling fans are being removed?

**A8 There are no ceiling fans in the existing space.**

Q9 Do we have a Count on how many existing emergency lights would need to be changed?

**A9 Replace existing.**

Q10 Will there be any other drawings issued for these three schools or have all the drawings been issued as per the original documentation.

**A10 All drawings have been provided.**

All other terms & conditions remain unchanged.

If you have any questions, please do not hesitate to contact the undersigned.

**Bidders are required to acknowledge all Addenda in the space(s) provided on the Bidder's Declaration or attach all Addenda issued to the Bid.**

Jennifer Moffatt  
Buyer  
jennifer.moffatt@granderie.ca