

# Addendum 1

Issued March 6, 2025

The following information changes the competitive process documents issued on Wednesday, February 19, 2025.

#### **CLOSING DATE CHANGE**

Change of closing date to Thursday, March 13, 2025, on or before 2:00:00 PM local time.

#### **GENERAL INFORMATION**

Item 1: Refer to RFT Document, Instructions to Bidders REMOVE and REPLACE Section 1.5 Project Schedule with below:

#### **1.5** PROJECT SCHEDULE

.1 The Successful Bidder will adhere to section GC 3.4 in regard to milestone dates set below.

.2 The following are Project milestone dates:

gym RTU preparation

a. Tender Issued	Wednesday, February 19, 2025
b. Site Walkthrough at 4:00 PM	Monday, February 24, 2025
c. Closing for Questions	Tuesday, March 4, 2025
d. Tender Closing at 2:00:00 PM	Thursday, March 13, 2025
e. Gym RTU shop drawings provided to Consultant	10 business days after awarded
f. Anticipated Construction Commencement	Friday, June 27, 2025
g. Substantial Performance	
i. Classroom 112 and Office 107/108	Friday, August 8, 2025
ii. Remaining work: Corridors, lobby,	Friday, August 15, 2025
gym RTU preparation for install	
iii. Gym RTU – Installation and commissioning	Friday, October 3, 2025
(approx. 26 weeks from shop drawing approval)	
h. Ready-for-Takeover	
i. Classroom 112 and Office 107/108	Friday, August 15, 2025
ii. Remaining work: Corridors, lobby,	Friday, August 15, 2025

.3 Classroom 112 and offices 107/108 need to be prioritized for completion as office staff will be working in the office and teachers will be in the classrooms. To be clean and paint ready by August 10, 2025, with no exceptions.

iii. Gym RTU – Installation and commissioning Friday, October 10, 2025



# 2025-107-P02082 Hess Street Elementary School Ground Floor Corridor Renovation and RTU Replacement Addendum 1

.4 Any Work remaining after the Substantial Performance of the Work date will need to be completed after hours and weekends and cannot be disruptive to the school and operations of the school in any way.

Item 2: See attached Addendum 1, AMRA J Architect Inc, March 6, 2025, (8 pages).

## **QUESTIONS AND RESPONSES**

- Q1 Please consider a closing date extension as we have other tenders closing same day or time. 13th or 18th preferred. Would be much appreciated thanks.
- R1 Refer to General Information Item 1.

**End of Addendum 1** 



905-920-5121

## Addendum No. 1

Project No.: 24-22

**Date:** March 06, 2025

**Project:** Hamilton-Wentworth District School Board

REFERENCE NO. 2025-107-P02082

Hess Street Elementary School Ground Floor Ceiling Replacement and

Lobby / Classroom Renovation Project

The following information supplements and/or supersedes the bid documents issued on\_February 19, 2025.

This Addendum forms part of the contract documents and is to be read, interpreted, and coordinated with all other parts. The cost of all contained herein is to be included in the contract sum. The following revisions supersede the information contained in the original drawings and specifications issued for the above-named project to the extent referenced and shall become part thereof. Acknowledge receipt of this Addendum by inserting its number and date on the Tender Form. Failure to do so may subject the bidder to disqualification.

#### 1. INTENT

1.1. This Addendum is issued prior to receipt of Bid to provide clarifications and revisions to the Drawings and Specifications. The following additional instructions shall apply to and govern the Bid Documents.

## 2. QUESTIONS AND ANSWERS

- Q1. Please provide specifications of interior screens arch. plans page A1.02 sections 2 and 3.
  - R1. Interior screen to be hollow metal with 12 mm tempered glazing
- Q2. Please provide contact info of base building fire alarm contractor.
  - R2. Fire Alarm Control and Testing Service Provider: Hamilton Fire Control. Fire Alarm and Security System Monitoring Service Provider: API Alarm Inc.
- Q3. On Dwg. A1.01 Demo note 3: Remove existing wood ceiling and pot lights c/w all support framing within area of display box. Maintain existing aluminum framing and its support to the existing structure above. Take care not to damage existing metal screen of display. Prepare area to receive new ceiling finish.

Addendum #1

Hess Street Elementary School Ground Floor Ceiling Replacement and Lobby / Classroom Renovation Project

# AMRA J ARCHITECTS INC. space design

## Addendum No. 1

www.aja.design info@aja.design 905-920-5121

How the demo wood ceiling and installing new ceiling can be accomplished without taking the Aluminum frame and glass?

- R3. The general contractor to determine the best approach for removing the existing wood ceiling and installing a new one while preserving the aluminum frame and glass. This includes assessing whether the existing metal screen needs to be temporarily removed to facilitate the work.
- Q4. In the door schedule frame is fire-rated hollow metal, and the glass is specified as 12mm laminated (Not Fire-Rated Glass). Can we use the 12mm laminate (6mm clear temp + 6mm clear temp) as per the architectural drawings, or should it be the 5mm fire-rated glass with fire-rating properties?
  - R4. Delete the fire rating for the door. Glazing to be 12 mm laminated 2x6mm tempered glass
- Q5. Detail 4/A1.02, the corners where the HM frame meets should be finished with aluminum cladding—please confirm if this is acceptable.
  - R5. Yes, that is acceptable.
- Q6. Please confirm the size and type of fire rated access doors required so we can provide pricing. Specification 08 31 13 lists 2 units under 2.3.2 and 2.3.3, which unit should we price?
  - R6. Coordinate size and locations of fire rated ceiling access doors with mechanical/electrical design type to be with Recessed Access Door With Drywall Flange
- Q7. In room 112 the designated substance report indicates the existing ceiling tiles contain asbestos. Please review and advise if the ceiling is to be abated and replaced with new. The drawing note on A1.03 says salvage and reuse celling components in this area.
  - R7. Existing acoustic ceiling tiles and grid components to be reused and modified as required for the new wall.
- Q8. Please provide the base building contractors which we have to carry.
  - R8. For base building contractors, refer to Specifications, Division 01 Construction Contact Site Information Sheet

Addendum #1

Hess Street Elementary School Ground Floor Ceiling Replacement and Lobby / Classroom Renovation Project

# Addendum No. 1



www.aja.design info@aja.design 905-920-5121

- Q9. Can you please advise if privacy film is to be applied by HWDSB? Or is it included in GCs scope?
  - R9. Privacy film is to be supplied and installed by HWDSB.
- Q10. Reference: Fire Alarm Who is the Base Bldg Fire Alarm, E1-00 R10. Refer to A2
- Q11. Reference: Drawing A1.03
  - Please confirm that Painting Scope is only the following:
  - 1. Paint Display Frame drawing 1/A1.02
  - 2. Paint HM Door & Frame, Drawing 1/A1.02
  - 3. Paint GWB Ceiling as per Room Finish Schedule
  - R11. Painting scope includes items listed above and:
    - New wall in classrooms 112-A & 112-B
    - All new surfaces/materials and
    - All surfaces disturbed by demolition/new construction
- Q12. Please clarify if work to be performed by unionized or non-unionized labor
  - R12. There is no preference about labour to perform the work
- Q13. Please provide contact info of base building fire alarm contractor
  - R13. See A2.
- Q14. Please provide specifications of interior screens arch. plans page A1.02 sections 2 and 3 (is it to be aluminum or hollow metal)
  - R14. See A1.
- Q15. Reference: Drawing M2-02 Who is the Base Bldg Roofing Contractor on this project?
  - R15. There is no base Building Roofing Contractor
- Q16. Reference: Hazardous Material Do you have a DSS report on the Hazardous Materials
  - R16. Refer to the Specifications, Division 01, Section 0300 Available Project Information

Addendum #1

Hess Street Elementary School Ground Floor Ceiling Replacement and Lobby / Classroom Renovation Project

## AMRA J ARCHITECTS INC. space design

## Addendum No. 1

www.aja.design info@aja.design 905-920-5121

Q17. We received a list of approved data caballing contractors for another HWDSB bid, could you please confirm that we can carry any data caballing contractor?

R17. Refer to Addendum 1 prepared by E & M Engineering Inc. attached.

Q18. Would you please provide me with the specifications for the VCT flooring, the existing wall base, and the height of the rubber base that will be installed on the partition?

R18. VCT Flooring to be Tarket VCT II, colour to match existing. Wall base to be 100 mm high.

## 3. MECHANICAL AND ELECTRICAL

Attached is Addendum # 1 (4 pages) prepared by E & M Engineering Inc.

**END OF ADDENDUM NO 1** 



6004 Osprey Blvd Mississauga, ON L5N 8K1 CANADA T: 289-426-3071 www.eandmconsultingeng.com

## Addendum No. 1

**E&M Project No.:** 24075 **Project:** HWDSB-P2024-2082 – Hess Street ES Renovation

**Date:** March 6, 2025

**<u>Prepared By</u>**: E&M Consulting Engineers Inc.

## **Requirements:**

The addendum forms part of the Contract Documents and amends the original Specifications and Drawings, as noted below.

Ensure that all parties submitting bids are aware of all items included in this Addendum.

This Addendum consists of 2 page(s) and Appendix Elect-Add-1.

## **Responses to Questions**

Items	Questions	Responses
1	Electrician has requested pictures of the switch board and name plates. Regarding the E-200 drawing note 5.	See attached photos in Appendix Elect-Add-1
2	We received a list of approved data caballing contractors for another HWDSB bid, could you please confirm that we can carry any data caballing contractor?	Only the board approved data cabling shall be used  COMU NETWORKS - MIKE ONEAL, 289-253-9289, MIKEJ.ONEAL@COMU.CA  CONNEX TELECOMMUNICATIONS INC ED BALIAN, 905-944-6516, ESTIMATING@CONNEXSERVICE.CA  M ARCOMM INTEGRATED BUSINESS SOLUTIONS - ADAM LUCIA, 416-938-3730, ADAM.LUCIA@TELECON.CA

## Addendum No. 1

Project Name: HWDSB-P02082 -Hess Street ES Renovation E&M Project No.24075 Date: March 6, 2025

		RAMCOM COMMUNICATIONS INC STEPHEN STIPAC, 647-404-5811, STIPACS@RAMCOM.CA  TBD TELECOM BY DESIGN INC JAMES PATARAN, 416-244-2525, ESTIMATING@TELECOMBYDESIGN.CA
3	Please provide information of base building BAS constructor if there is one	Jake Rendulic Siemens Canada Limited Account Executive – SI Buildings RC-CA SI RAM TOR S-AUTO 1577 North Service Road East L6H 0H6 Oakville, ON Mobile: 905-541-7433 mailto: jake.rendulic@siemens.com



